THE HUT



COMPONENTS LIST – Panels and Parts pictures are contained in Installation Instructions.

Ensure you have all parts before leaving your distributor or commencing installation.

PANELS	DESCRIPTION	NOTES	QTY	CHECK
Floor	2595mm deep, 1800mm wide. 4	Particleboard may be supplied as	1	
Picture 2A	Joists with particleboard and	loose sheet to minimise panel		
	decking attached.	weight.		
Front	1840mm long, 1520mm high.	Decking attached to bottom	1	
Picture 3A	Includes door and 2 windows.	ready for fixing directly to joists.		
Back	1840mm long, 1520mm high.	Cladding protrudes 22mm past	1	
Picture 6A	Cladding stops attached on each	bottom face.		
	end.			
Side Number 1	1800mm long, 1520mm high.	Cladding protrudes 22mm past	1	
Picture 4A	Includes window in centre.	bottom face.		
Side Number 2	1800mm long, 1520mm high.	Cladding protrudes 22mm past	1	
Picture 5A		bottom face.		
Gable Tops X2	2 triangular shaped panels	Cladding protrudes 22mm past	2	
Picture 8A	1800mm long.	bottom face.		
Balustrade	1800mm long, 1540mm high.	Decking attached to bottom	1	
Picture 9A		ready for fixing directly to joists.		
Roofs Picture10	2630mm long, 1100mm wide.	Cubby roof.	2	
PARTS				
Ridge Beam	Steel beam with capping 2630mm		1	
Picture 10A & B	long.			
Perspex	6 Perspex panels for windows – All	2 panels per window. Remove	6	
Picture 16A	505mm high, 4 X 260mm wide	protective sheet before fitting.		
	(front), 2 X 290mm wide (side).			
Door Handle	2 Wooden knobs with attaching	1 pair per door.	1	
	thread.		pair	
Facia	70mm x 20mm, 1130mm long.	Fit to ends of cubby roof panels.	4	
Picture 14A		2 pair, left and right.		
FIXING SCREWS		- Communication of the Communi		
Wing Tip	40mm long Phillips head.	*	12	
Particleboard	50mm long Phillips head.	all conse	20	
Tech	20mm long 8mm Hex head.	* mmmmm	12	
	45mm long 8mm Hex head.	S STATE OF THE STA	16	
Bugle	70mm long Allen key head.	→	20	

BEFORE COMMENCING INSTALLATION:

- 1. Read all instructions thoroughly.
- 2. Ensure the site is level.
- 3. Identify and segregate all components.
- 4. Gather required tools.

TOOLS REQUIRED:


Variable speed drill with 3 bits – 8mm Hex socket, 5mm Allen key, and a Phillips head. Safety glasses. For site levelling, if required – Shovel, level, and a straight edge. Ensure underground services are clearly marked. Tape measure.



INSTALLATION INSTRUCTIONS – THE HUT

1. Ensure site is level and even. If not cut and fill. Use a straight edge and level to remove any uneven areas. Pack down firmly.

2. Place floor in desired position. Fit loose particleboard sheet squarely into position on joists. Ensure tight fit on join. Use 50mm Phillips head particleboard screws to attach the board to the floor joists – 3 screws per joist, one 50mm from each edge of the sheet and one in the centre.







4. On the remaining 3 walls the cladding overhangs 20mm on the bottom of the wall. The overhang passes beside the particleboard floor, allowing the bottom plate of the walls to rest directly on the floor. The two side walls are interchangeable. Place the side wall with the window into your preferred side position and onto the particleboard floor, square to and against the front wall. Align the outermost points of the cladding on the side wall against the cladding stop on the front wall. Using two 70mm bugle screws, attach the side wall to the front wall through the corner wall studs.



- 5. Attach the opposite side wall as per step 4.
- 6. Fit the back panel between the two side walls and onto the particleboard floor. Fix in each corner to the side walls as above.



7. After ensuring the bottom of the front wall is still firmly positioned hard against the particleboard, fix the walls to the using two 70mm bugle screws through the bottom plate of wall into the flooring joists.





floor each



8. Place a gable top onto the front wall. Centre the gable top on the wall, ensuring it finishes flush with the wall on either end. The cladding overhang on the gable top should be pulled firmly against the front wall cladding. Fix into position using two 70mm bugle screws placed approximately 400mm from each end. Screw up through the top plate of the wall into the bottom

plate of the gable top.





9. Place the balustrade directly onto the joists at the front of the floor decking. Align the face of the bottom board on the balustrade with the outermost point of the floor facia. The measurement between the back of the balustrade end posts and the edge of the cladding stop on the front wall should be 610mm. If required adjust balustrade position to achieve this distance. Using 50mm particleboard screws through the bottom plate of the balustrade, secure the balustrade to 9A the floor.



10B

10. Lay the ridge beam and one 2635mm X 1100mm roof panel upside down on the ground. Align the ends and push the roof panel into the beam until firmly home. Screw through the beam into the channel frame of the roof panel using four 20mm tech screws at equal spacings along the

beam.



11. Position the roof onto the side of the gables ensuring the ridge beam is centred on the gable peak. The roof should align at the front with the outermost point of the front balustrade post. (ie. overhang from the cladding stop on the side of the cubby front wall to the end of the roof should be 680mm.) Screw through the roof panel into the top of the gable using three 45mm tech screws at equal spacings on each end. Lift the other roof into position on the gables, align the roof ends, and push firmly home into the ridge beam. Screw through the roof panel into the top of the gable using three 45mm tech screws at equal spacings on each end. Screw through the roof panel into the top of the back and front walls using four 45mm tech screws at equal spacings on each roof panel.



Page 3 of 4





12. Secure the roof into the beam from inside the cubby using four 20mm tech screws at equal spacings along the beam length, screwing through the beam and into the channel frame of the panel.



roof

13A

13. Using four 20mm tech screws, screw through the edge corners of the flashing on the ridge beam into the roof panel channel.

matched pairs, each Position the facias the top of the roof beam. Screw roof using three and one in the



14. Cubby roof facias come as two containing a left and a right hand facia board. ensuring the top edge of the facia is flush with panel, with one end central against the ridge through the facia into the channel frame of the 40mm wing tip screws, one toward each end centre.

- 15. Unscrew the door handles and pass the thread through the hole provided in the door frame. Tighten the handles on either side of the door onto the thread.
- 16. Remove the protective cover sheets from the window perspex. Place one end of the sheet into the bottom inside groove of the window frame. Flex the sheet to allow it to enter into the top inside groove. Use the same process to fit a second perspex sheet into the outside groove. Repeat for other windows.



